No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	II. CONSTRUCTING MASONRY WEIR CRUST AT R.L. 50·00.				
1	Earthwork excavating foundation for masonry and clearing draft and approach	C.yd.	0 3 0	1,147	
2	Concrete in surki mortar for filling in foundation	C.ft.	0 4 6	170	
3	Size stone in surki mortar	,,	0 5 0	238	
4	Providing and fixing burnt stone slabs, 6" thick	S.ft.	0 8 0	146	
5	Rough stones apron with jelly packing and wedging	C.yd.	1 8 0	37	
6	Cement pointing	Sqr.	4 0 0	2·00	
	III. CONSTRUCTING MASONRY SLUICE SILL AT R.L. 45·00.				
1	Cutting open the bund and refilling with consolidation	C.yd.	0 4 6	31	
2	Earthwork excavating foundation for masonry	,,	0 3 0	30	
3	Concrete in surki mortar	C.ft.	0 4 6	85	
4	Size stones in surki mortar	,,	0 5 0	195	
5	Providing and fixing slabs 6" thick	S.ft.	0 8 0	90	
6	Cement pointing	Sqr.	4 0 0	2·00	
7	Providing and fixing 6" dia. C.I. pipes, including carting, cement jointing, cost of pipes, etc., complete	R.ft.	2 0 0	33	
8	Drilling holes in slabs	Each	1 0 0	3	
9	Providing and fixing teakwood plug and iron rod with locking arrangements, etc., complete	L.S.	.. ..	10 0 0	

D. A. HUKERI,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 13th January 1938.

The attention of the public is hereby invited to the advertisement published on pages 87 and 88, Part VI of the *Mysore Gazette*, dated the 20th January 1938, calling for tenders for the construction of a Police Station with compound wall and a set of latrines at Bhadravati, Shimoga Taluk.

Last date for receiving tender is 31st January 1938, 3 P.M.

P. SUBBA RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

DEPARTMENT OF AGRICULTURE.

OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, BANGALORE CIRCLE, BANGALORE.

Notification dated 13th January 1938.

It is hereby notified that the Mango Crop on 158 trees of the Ramakrishna Krishi Sala at Kachanaikanahalli, Anekal Taluk, will be sold by public auction at the Sala premises on 10th February 1938 at 2 P.M., by the Head Master of the Sala, and the highest bidder is requested to pay up the entire amount of his bid on the spot and make his own arrangements for removing the crop. In default, a resale will be held at his own risk and any loss sustained therefrom will be recovered from him as arrears of land revenue.

B. SHANKARA RAO BADAMI,
For *Assistant Director.*